



**ENLARGED DEMOLITION FLOOR PLAN – MECHANICAL PIPING**

SCALE: 3/16" = 1'-0"

**ASBESTOS AND LEAD PAINT NOTE**

AN ASBESTOS INSPECTION WAS PERFORMED AND ASBESTOS CONTAINING MATERIALS WERE FOUND GENERALLY IN THE AREAS INDICATED IN THE ASBESTOS SURVEY/INSPECTION REPORT WHICH IS AVAILABLE TO THE CONTRACTOR(S) FOR HIS INFORMATION. ASBESTOS CONTAINING MATERIALS HAVE BEEN REMOVED UNDER A SEPARATE CONTRACT.

A LEAD-BASED PAINT INSPECTION WAS PERFORMED AND LEAD-BASED PAINT WAS FOUND IN THE AREAS INDICATED. THE CONTRACTOR SHALL BE RESPONSIBLE WITH ALL REQUIREMENTS OF THE VIRGINIA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS LEAD-BASED PAINT PROTECTION OF WORKERS.

**DEMOLITION NOTES THIS SHEET**

- 1 REMOVE HWS/HWR AND CWS/CWR PIPING, HANGERS, AND SUPPORTS COMPLETE TO POINT INDICATED.
- 2 REMOVE WALL MOUNTED THERMOSTAT AND CONTROL LINES COMPLETE.
- 3 REMOVE UNIT HEATER, HANGERS, AND SUPPORTS COMPLETE.



**GRAPHIC SCALES**

3/16" = 1'-0" 0' 5' 10' 20'

**nbij** ARCHITECTURE  
A Professional Limited Company  
GROVE PARK SQUARE  
11537-B NUCKOLS ROAD  
Richmond, Virginia 23069  
☎ (804) 273-9611 fax: (804) 273-9843



**RAPPAHANNOCK  
COMMUNITY COLLEGE**  
CAMPUS RENOVATIONS  
WARSAW + GLENN'S, VIRGINIA  
PC: 260-17712

**GLENN'S CAMPUS  
DEMOLITION FLOOR  
PLAN – MECHANICAL PIPING**

Date: JANUARY 13, 2010

REVISIONS

NO. DATE

Sheet

**MD2.4G**

File Number

XX

